EXTRA ITEM

RATE LIST

Scanned by CamScanner

BRUHAT BANAGLORE MAHANAGARA PALIKE

Byatarayanapura Sub Division

EXTRA ITEM RATE LIST

Name of the work : Package No.03(Package consists of 21 works)

Agency: CGC INFRA PROJECTS PVT LTD CGC INFRA PROJECTS PVT LTD (Sri C.G Chanadrappa # 1c 301, 3rd main block HRBR Layout kalyan nagar Bangalore 560043)

Sl No	Item Of Work	Unit	Estimate qty	Rate	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
1	2	3	4	5	6	7	8	9	10	11
E1	Providing and fixing RCC Precast cover slab of 250mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	sqm	48.12	5418.00	260714.16	Additonal Item	No	Savings in Estimate	Approved Data Rate	
E2	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	sqm	354.15	2337.00	827648.55	Additonal Item	No	Savings in Estimate	Approved Data Rate	
E3	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc., complete as per specifiocation. (P. No. 45 / I. No. 7.37 of CSR 2018-19)	sqm	18.38	3416.21	62772.87	Additonal Item	No	Savings in Estimate	Yes	
E4	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (Page No. 123 Item No. 15.74 of SR 2018-19)	sqm	36.75	107.75	3959.78	Additonal Item	No	Savings in Estimate	Yes	

Scanned by CamScanner

E5	KSRRB M800 Road markers/ Road stud , KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS (Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering thje lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97-DO III Dt 11.06.1997.The height, width and length shall not exceed 50mm, 100mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree.The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19mm and height not less than 30mm)from the body is to be a minimum value of 500kg. Fixing will be by drilling holes on the road for the shanks to go inside, without ails and using epoxy resin based adhesive as per manufacture's recommendation and complete as directed by the engineer.(P.No-187,I No-24.41)	Nos	188.80	382.23	72164.16	Additonal Item	No	Savings in Estimate	Yes	
	TOTAL EIRL AMOUNT				**1227259.51**					
	AMOUNT IN WORDS									

PERCENTAGE OF EXCESS OVER AMOUNT PUT TO TENDER

$$\frac{\text{EIRL}}{\text{Amount put to Tender}} = \frac{1227259.51}{97474200.27} \times 100 = 1.26\ \%$$

Asst.Engineer

Asst.Executive Engineer

Assistant Executive Engineer,
Kodigehalli Sub Division,
Yelahanka Zone, B.B.M.P.,
Bangalore.

Executive Engineer

ಮುಖ್ಯ ಅಧಿಕ್ಷಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Scanned by CamScanner